6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing A.-V. School at Channarayapatna.

No.	Items of work	Per	Quantity
1	Removing the existing roof with tiles, reepers, etc., and stacking	Sq.	22·00
2	Dismantling masonry walls	C. ft.	1,125
3	Sundry items that may be found necessary during dismantling, etc.	Lump	sum.
4	Earthwork excavating for foundation	C. yd.	87
5	Stone in clay, foundation	C. ft.	2,626
	Do basement	,,	1,079
6	Burnt brick in clay superstructure	,,	4,859
6a	Do in mortar do	,,	982
7	Do archwork	,,	113
8	Burnt stone slabs, dressed, 4" to 6" thick	S. ft.	295
9	Fixing old slabs	,,	151
10	Forming caps and bases of pillars in verandah	Each	8
11	Moulding with pillasters around arches, etc.	Lump	sum.
12	New teakwood pannelled doors with fastenings, etc.	S. ft.	236
13	New teakwood windows with iron bars, iron work and glazed shutters, etc.	,,	63
14	Teakwood circular ventilators with glazed shutters	,,	48
15	Burnt stone slab pillars nicely dressed and grooves cutting and fixed	,,	72
16	Removing and refixing old doors and windows	Each	10
17	Teakwood, wrought and put up complete	C. ft.	267·90
18	Refixing old bressummers and rafters to front verandah	Lump	sum.
19	Stone brackets to support purlins of front verandah	Each	24
20	Roofing with 1st class Mangalore tiles, teak reepers, etc., complete	Sq.	32·30
21	Roofing with old Mangalore tiles, teak reepers, etc., complete	,,	22·00
22	Ridge tiles set in mortar and pointed	R. ft.	80
23	Resetting old ridge tiles in motar and pointed	,,	65
24	Providing zinc sheets and planking for valleys and mortar bands	S. ft.	309
25	Teakwood eave board.	R. ft.	356
26	Refixing old eave board	,,	75
27	Teakwood finials	Each	4
28	Do pendants	,,	8
29	Chunam plastering	Sq.	104·40
30	White and colorwashing	,,	104·40
31	Flooring with first class Mangalore tiles, 9" square over 3" concrete bed and cement pointing, complete.	,,	13·90
32	Do with Cuddapah slabs over 3" concrete bed and cement pointing, etc., complete.	,,	4·00
33	Painting doors and windows	,,	22·04
34	Chunam borders over roof	R. ft.	326
35	Front pediment work as per plan	Lump	sum.
36	Repairs to existing building including white and colorwashing and unforeseen items, etc.	Lump	sum.
37	Clearing site and levelling ground and removing high ground in rear, filling ditch in front and forming play ground, etc.	Lump	sum.

K. R. SESHACHAR,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 18th March 1916.

CALLING FOR TENDERS.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 5 P.M. on 29th April 1916, for constructing a Police Station and lines at Chandragutti, Sorab Taluk.

2. An approximate estimate of quantities is given below.

3. These quantities are not guaranteed.

4. The work has to be done so as to suit the allotments granted from time to time.

5. The work should be completed by the 1st April 1917.

6. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M., on all office working days.

7. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

8. The tenders should be accompanied by statements of the Forms A and B given below, showing clearly the rates at which the different items specified will be executed.

9. All lump sum items have got to be settled on the spot with the officer in charge, before undertaking the work.

10. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "tender for constructing a Police Station and lines at Chandragutti, Sorab Taluk," in default of which, tenders will be rejected.

11. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

12. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

13. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course.

14. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

15. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

16. All royalty, tolls, etc., claimed will have to be paid for by the contractor.

17. Materials supplied by the Government, if any, will have to be accepted by the contractors and used, and a charge of 10 per cent for supervision on the actual cost will be levied of all such materials.

18. The progress stipulated should, if possible, be very nearly :—

	Rs.
May 1916	1,000
June ,, ...	500
July to October	Nil
November	500
December	1,000
January	1,000
February	2,000
March	2,000
April	500

in default of which, a fine of 5 per cent on short progress will be leviable, and the contract may be cancelled, if there be a failure in three successive months to show the stipulated progress.

A.

Abstract estimate for constructing a Police Station at Chandragutti, Sorab Taluk.

No.	Items of work	Per	Quantity
1	Clearing site and levelling ground	Lump sum	Rupees
2	Earthwork, excavating, foundation and filling basement	C. yd.	37
3	Burnt stone in clay	C. ft.	1,710
4	Burnt brick in clay	Do	1,831
4a	Do in chunam	Do	441
5	Burnt stone slabs, dressed	S. ft.	238
6	Plastering with mortar	Sq.	43·60
7	Burnt brick in mortar coping with plastering	R. ft.	67
8	White and colourwashing	Sq	43·60
9	Honnewood work wrought and put up	C. ft.	49·00
10	Roofing with 1st class Mangalore tiles, with teak reepers 2"×1"	Sq.	11·20
11	Ridge tiles set in mortar	R. ft.	40
12	Teakwood ceiling plank, ½" thick tounged and groved including fixing complete	S. ft.	210
13	Honnewood doors battened with necessary iron fittings and iron clamps ..	Do	88
14	Do door for lock-up with iron bars, etc., as per type design ...	Do	49
15	Do iron doors with iron bars ½" dia. battened shutters inclusive of rings and iron clamps, etc.	Do	85
16	Do ventilators with expanded metal ½" dia. iron bars	Do	11
17	Cutting grooves in slabs and dressing faces	No.	2
18	Honnewood eave board	R. ft.	128
19	Wood oiling to wood work	Sq.	6·00
20	Silicate painting and coating with varnish	Do	5·81
21	Tarring to wood work and also to latrine...	Do	3·00
22	Flooring with Mangalore tiles over 3" concrete bed and cement pointing	Do	3·92
23	Wooden railing of teakwood as shown on plan inclusive of frame work and fixing them on retaining wall with painting.	R. ft	52
24	Teakwood gate, ordinary, with shutter inclusive of iron fittings and painting complete.	S. ft..	16
25	Flooring with Cuddappah slabs 1½" thick over 3" concrete and cement pointing	Sq.	1·52
26	Constructing V-shaped drain with surki concrete and cement plastering, etc., complete.	R. ft.	100
27	Filling with gravel and consolidation	C. yd.	11
28	Binding wall on roof complete	R. ft.	48
29	Teakwood finials	Each	2
30	Do pendants	No.	4
31	Constructing latrine and drain pipe, etc.	Lump sum	Rupees

B.

Abstract estimate for constructing Police Lines at Chandragutti, Sorab Taluk.

No.	Items of work	Per	Quantity
1	Clearing site and levelling ground	Lump sum	ten rupees
2	Earthwork excavating foundation and filling in basement	C. yd.	76
3	Stone in clay foundation and basement	C. ft.	2,915
4	Burnt brick in clay	Do	3,051
4a	Do in mortar	Do	856
5	Burnt stone slabs, dressed and fixed, 6" thick	S. ft.	548
6	Plastering with mortar	Sqr.	91·00
7	White and colourwashing	Do	91·00
8	Hannewood work	C. ft.	115·00
9	Roofing with 1st class Mangalore tiles with teak reepers	Sqr.	25·20
10	Ridge tiles set in mortar	R. ft.	70
11	Flooring with Cuddappah slabs 1½" thick over 3" concrete and cement pointing	Sqr.	5·34
12	Do 1st class Mangalore tiles over 3" concrete and cement pointing	Do	8·35
13	Hannewood ornamental eave board	R. ft.	362
14	Do battened door with hinges and iron clamps, etc., complete	S. ft.	468
15	Do windows with ½" dia. iron bars and battened shutters and iron clamps, etc., complete.	Do	53
16	Do ventilators with expanded metal, iron bars and iron clamps and battened shutters.	Do	23
17	Painting doors and windows	Sqr.	16·16
18	Tarring wood work and latrine walls	Do	4·50
19	Binding wall	R. ft.	61
20	Coping with brick in chunam plastering	Do	220
21	Smoke escapes	each	6
22	U-shaped drain with surki concrete and cement plastering, etc.	R. ft.	230
23	Wood oiling to wood work	Sqr.	19·54
24	Gravel filling with consolidation	C. yd.	13
25	Providing 1½" out-let pipes	No.	12
26	Constructing seats in latrine	Lump sum	Rupees,
27	Finials and pendants	Do	

V. R. NIJAGAL,
Executive Engineer.

KADUR DIVISION.

The following amounts are outstanding unadjusted in the accounts of the Executive Engineer, Kadur Division and notice is hereby given that the amounts will be credited to Revenue if not claimed within three months from this date.

	Rs.	a.	p.
1. Lakshminarayana, for repairing Police Station and Lines and P. W. Officers' quarters at Balgady	25	3	1
2. Varadarajulu Naidu, for repairing Narve-Nagalapur road	53	0	0
3. Rangappa, for repairing Sandal koti at Chikmagalur	7	8	1

K. PONNAPPA,
Executive Engineer.

MYSORE GOVERNMENT STATIONERY DEPARTMENT.

Notice dated 20th March 1916.

TENDER FOR THE SUPPLY OF MISCELLANEOUS ARTICLES.

Sealed tenders for the supply of all or any of the undermentioned articles during the official year 1916-17, will be received by the Superintendent of Stationery, up to 2 P.M., on Monday the 24th April 1916.

No.	Description of articles	Approximate quantity required
1	Blue-black ink powder	2,750 packs
2	Red ink powder	2,000 „
3	Straw boards, 2 lbs. each	10,000 boards
4	„ 3 „ „	2,000 „
5	„ ½ lb. each	2,000 „
6	Sheepskins, royal size, 21"×28"	600 skins
7	Finger printing apparatus, consisting of zinc plate mounted on bevel edged teakwood plank measuring 7"×5"×1" with rubber roller 3" long and ½ lb. ink tin	300 sets
8	Pocket set of the Finger printing apparatus consisting of a zinc plate roller (rubber) packed suitably in a small tin box measuring not more than 4½"×3"×¾"	33 „

N.B.—Each pack of item Nos. 1 and 2 must contain 6 packets and each such packet should produce one pint of best fluid ink.